

Clin #	Item	Description	UM	Unit Price	Install Price	Total Price
1	Category 6 plenum cable	Material Pricing includes 1000' reel of Cat 6 plenum Cable. The labor pricing includes the installation of 1000' of Cat 6 cable in standard drop ceiling with no terminations or cable support	CLF	\$ 0.28	\$ 1.43	\$ 1.71
2	Category 6 Connector RJ45-Modular Plug	Material pricing includes one Cat 6 RJ45 Modular Plug (male). The labor pricing includes the termination of one Cat 6 RJ45 male modular plug. Testing of connection is also included in labor pricing	EA.	\$ 2.95	\$ 84.50	\$ 87.45
3	Category 6 Jack RJ45	Material pricing includes one Panduit Cat 6 jack. The labor pricing includes the termination of one Cat 6 jack. Testing of connection is also included in labor pricing	EA.	\$ 6.75	\$ 84.50	\$ 91.25
4	Faceplate	Material pricing includes one 4 Panduit port faceplate and one dry wall ring to attach faceplate to. No conduit/wiremold has been included. Labor pricing includes the mounting of 4 jacks into faceplate and attaching faceplate to wall via dry wall ring	EA.	\$ 4.75	\$ 37.50	\$ 42.25
5	Patch Panel Port	Material pricing includes one Cat 6 48 port patch panel with one 2RU Horizontal Wire Manager. Labor pricing includes the mounting of patch panel to existing rack and the termination of one Cat 6 cable. Testing is also included in labor pricing	EA.	\$ 450.00	\$ 84.50	\$ 534.50
6	Hanger/Support	Material pricing includes installing one 2" hook to building structure. No sleeves, innerduct, wire tray, conduit, has been included in material pricing. Labor pricing includes installation of one 2" hook to building structure.	EA.	\$ 4.25	\$ 7.50	\$ 11.75
7	FIBT-S3A-114 transmitter	Material pricing includes one FIBT-S3A-114 Transmitter. Labor pricing includes the mounting of one transmitter to the wall. Testing is also included in labor pricing	EA.	\$9,105.50	\$ 84.50	\$ 9,190.00
8	FOC-116U-SA fiber splitter	Material pricing includes one FOC-116U-SA fiber splitter. Labor pricing includes the mounting of one splitter to the wall. Testing is also included in labor pricing	EA.	\$742.89	\$ 37.50	\$ 780.39
9	FRRA-S4S-860-43P receivers	Material pricing includes one FRRA-S4S-860-43P receiver. Labor pricing includes the mounting of one receiver to the wall. Testing is also included in labor pricing	EA.	\$1,291.46	\$ 84.50	\$ 1,375.96
10	24F Single Mode Fiber(200ft)	Material Pricing includes 1000' reel of Fiber plenum Cable. The labor pricing includes the installation of 1000' of Cat 6 plenum cable in standard drop ceiling with no terminations or cable support	EA.	\$1,170.00	\$ 37.50	\$ 1,207.50
11	ST 50/125 CONNECTORS	Material pricing includes one ST 50/125 CORNING Connector. The labor pricing includes the termination of one ST CORNING Connector. Testing of connection is also included in Labor pricing	EA.	\$1.11	\$ 84.50	\$ 85.61
12	COAX Cable CATV	Material pricing includes one CATV cable. The labor pricing includes the termination of one CATV cable. Testing of connection is also included in labor pricing	EA.	\$1.11	\$ 84.50	\$ 85.61
13	COAX Connectors	Material pricing includes one COAX CONNECTOR Connector. The labor pricing includes the termination of one COAX Connector. Testing of connection is also included in labor pricing	EA.	\$1.63	\$ 84.50	\$ 86.13
14	Label	Material pricing includes label tape required for proper labeling at the faceplate, patch panel and cable labels required every 50' of the cables. Labor pricing includes the installation of labels for faceplates at the workstation, patch panel and every 50' of cables based on a 200' cable run	EA.	\$ 4.15	\$ 25.00	\$ 29.15
	OPTIONAL LINE ITEM PRICING- BASE YEAR - PRICING BASED ON NORMAL BUSINESS HOURS, OPTIONAL AFTER HOURS PRICING AND RATES HAVE BEEN INCLUDED.					
15	Panduit Category 6 110 High Density Block	Material pricing includes one Panduit Cat 6 108 port wall mounted 110 block kit. Labor pricing includes installation of 110 block to wall and the termination of one Cat 6 cable to 110 block	EA.	\$ 225.00	\$ 84.50	\$ 309.50
16	Panduit Category 6 24 port patch panel	Material pricing includes one Cat 6 24 port patch panel with one 1RU Horizontal Wire Manager. Labor pricing includes the mounting of patch panel to existing rack and the termination of one Cat 6 cable. Testing is also included in labor pricing	EA.	\$ 250.00	\$ 84.50	\$ 334.50
17	Panduit LD10 wiremolding with box and misc connectors	Material pricing includes one 10' stick of Panduit LD10 wiremold, 1 Panduit wall box, and misc connectors/hardware. Labor pricing includes installation of one 10' stick of Panduit LD10 wiremold to wall or building structure along with box and misc connectors/hardware.	EA.	\$ 33.00	\$ 68.25	\$ 101.25
18	2" Firestop Sleeve Installation (Drywall)	Material pricing includes one 2" pre-manufactured firestop sleeve. Labor pricing includes installing 2" sleeve into a drywall wall.	EA.	\$ 39.50	\$ 49.50	\$ 89.00
19	4" Firestop Sleeve Installation (Drywall)	Material pricing includes one 4" pre-manufactured firestop sleeve. Labor pricing includes installing 4" sleeve into a drywall wall.	EA.	\$ 72.75	\$ 49.50	\$ 122.25
20	2" Firestop Sleeve Installation (Block/Concrete)	Material pricing includes one 2" pre-manufactured firestop sleeve. Labor pricing includes installing 2" sleeve into a block/concrete wall no thicker than 12"	EA.	\$ 39.50	\$ 100.00	\$ 139.50
21	4" Firestop Sleeve Installation (Block/Concrete)	Material pricing includes one 4" pre-manufactured firestop sleeve. Labor pricing includes installing 4" sleeve into a block/concrete wall no thicker than 12"	EA.	\$ 72.75	\$ 100.00	\$ 172.75
22	1" plenum innderduct-wire tray installation	Material pricing includes no more than 75' of 1" plenum innderduct to run between wire trays with associated bushings, connectors, and couplers. Labor pricing includes the installation of up to 75' of 1" plenum innderduct and the installation of associated bushings, connectors, and couplers.	EA.	\$ 185.00	\$ 160.00	\$ 345.00
23	Fire stop - Riser/Vertical Penetration (Hilti Brand)	Material pricing includes firststopping materials (putty, caulk, muffs,etc) into one existing or new 4" vertical penetration. Labor pricing includes installation to properly firestop existing or new vertical penetration up to 4".	EA.	\$ 170.00	\$ 235.00	\$ 405.00
24	Fire stop - Wall Penetration (Hilti Brand)	Material pricing includes firststopping materials (putty, caulk, muffs,etc) into one existing or new wall penetration. Labor pricing includes installation to properly firestop existing or new wall penetration with conduit sleeves or cable trays.	EA.	\$ 170.00	\$ 190.00	\$ 360.00
25	New 19" floor mount rack with vertical managers	Material pricing includes one 19" 2 post rack with 2-4" vertical managers, and grounding materials. Labor pricing includes installation of rack, 2 vertical managers. Rack will be secured to the floor and properly grounded.	EA.	\$ 765.00	\$ 275.00	\$ 1,040.00
26	Category 6 Patch cords no longer than 7' - Closet End	Material pricing includes one Cat6 patch cord no longer than 7'. No labor has been included. Cables will not be patched into government network equipment.	EA.	\$ 4.25	\$ -	\$ 4.25
27	Category 6 Patch cords 14'-Workstation end	Material pricing includes one Cat 6 patch cord no longer than 14'. Labor pricing includes installing patch cord from jack at workstation and cabling by PC/Network equipment. Cables will not be patched into government pcs/network equipment.	EA.	\$ 6.50	\$ 15.00	\$ 21.50
28	Category 6 Cable Installation - 1-QUAD (2 voice/2 data) location - 300ft or less - Normal business hours M-F 8-5	Materials include Cat 6 cable up to 300', 4 Cat 6 jacks, faceplate, and jhook support every 5'. Labor pricing includes installation of 4 cat 6 cables to one location with jhook support every 5', terminating of cables on both ends and testing.	EA.	\$ 570.00	\$ 350.00	\$ 920.00
29	Category 6 Cable Installation - 1-QUAD (2 voice/2 data) location - 300ft or less - After normal business hours	Materials include cable up to 300', 4 Cat 6 jacks, and faceplate. Labor pricing includes installation of 4 cat 6 cables to one location, terminating of cables on both ends and testing.	EA.	\$ 570.00	\$ 490.00	\$ 1,060.00
30	Engineering Support- Normal Business Hours	On site additional engineering support during normal business hours.	HR.	\$ -	\$ 119.65	\$ 119.65
31	Engineering Support After Normal Business Hours	On site additional engineering support after normal business hours.	HR.	\$ -	\$ 179.50	\$ 179.50
32	Cabling Technician- Normal Business Hours	Onsite Cabling Technician for work not identified in line item pricing. Rate is for normal business hours.	HR.	\$ -	\$ 65.00	\$ 65.00
33	Cabling Technician- After Normal Business Hours	Onsite Cabling Technician for work not identified in line item pricing. Rate is for after normal business hours.	HR.	\$ -	\$ 97.50	\$ 97.50
34	Cable Task Manager	Onsite project manager	HR.	\$ -	\$ 56.55	\$ 56.55
35	Cable Instalation Specialist	Onsite Specialist who over see the installation	HR.	\$ -	\$ 27.95	\$ 27.95
36	Additional Material Markup	Any additional materials that are needed and not identified in line item pricing will receive this additional mark up to cost of materials.	HR.	15%		\$ 0.15